

# Attachment B. 2023 Safe Oakland Streets (SOS) Initiative Annual Report

## 2023 Rapid Response Investigations and Implementation Status

OakDOT mobilizes its Rapid Response Program primarily in response to fatal traffic crashes. A Rapid Response investigation is activated following fatal traffic collisions involving vulnerable populations, including but not limited to children, seniors, people with disabilities, pedestrians, and bicyclists. The Program involves an engineering assessment that is separate and informed by police investigation of the crash, focused on the prevention of future loss of life.

Identified improvements are delivered through the Rapid Response Program (via a maintenance treatment or quick-build improvement) or through other existing programs, such as the paving program or capital improvements when there are existing plans for improvements as part of a larger project. In some cases, the engineering investigation may determine that the crash and resulting fatality was not preventable through engineering treatments, and no engineering action is identified for these cases.

Numerous Rapid Response investigations in 2023 were related to fatalities on International Boulevard. Improvements developed from these investigations have been folded into the International Boulevard Quick Build Project.

The following table includes the status of all Rapid Response investigations activated in response to 2023 fatalities or collisions.

2023 Rapid Response Investigations and Status

| Incident Date | Location                   |                             | Fatal/Injury Category                   | Rapid Response Improvement   | Status      | City Council District |
|---------------|----------------------------|-----------------------------|---|--|-------------|-----------------------|
|               | Major Street               | Cross Street                |   |  |             |                       |
| 1/22/2023     | International Boulevard    | 2000 Block                  | 1 Pedestrian Fatality                   | Will be part of AC Transit/OakDOT International Blvd Quick Built Project   | In Progress | 2                     |
| 1/26/2023     | High Street                | Westbound 580 On-Ramp       | 1 Bicyclist Fatality                    | Restripe crosswalk and install of hardened centerline  | In Progress | 4                     |
| 2/18/2023     | International Boulevard    | 34th Avenue                 | 2 Pedestrian Injury                     | Will be part of AC Transit/OakDOT International Blvd Quick Built Project   | In Progress | 5                     |
| 2/19/2023     | Harrison Street            | 19th Street                 | 1 Pedestrian Fatality                   | Prune tree to increase traffic signal visibility   | Installed   | 3                     |
| 3/23/2023     | MacArthur Boulevard        | Magee Avenue                | 1 Pedestrian Injury                     | No engineering action identified   | n/a         | 4                     |
| 4/22/2023     | Joaquin Miller Road        | Skyline Boulevard           | 1 Passenger Fatality                    | Install additional traffic signs and markings, including upgrading all crosswalks to high-visibility style   | Installed   | 4                     |
| 5/17/2023     | 98th Avenue                | D Street                    | 1 Bicyclist Fatality                    | No engineering action identified   | n/a         | 7                     |
| 5/19/2023     | 35th Avenue                | E. 16th Street              | 1 Pedestrian Fatality                   | Install enhanced school zone and pedestrian signage and hardened centerline; refresh high-visibility crosswalk markings; replace 8" signal heads with 12" signal head; and install individual accessible pedestrian push buttons | Installed   | 5                     |
| 6/3/2023      | International Boulevard    | 91st Avenue                 | 1 Pedestrian Fatality                   | Will be part of AC Transit/OakDOT International Blvd Quick Built Project   | In Progress | 7                     |
| 6/16/2023     | Foothill Boulevard         | Vicksburg Avenue            | 1 Pedestrian Fatality                   | Install post/paint island in center turn lane, hardened centerline, and red curbs  | Installed   | 5, 6                  |
| 6/24/2023     | International Boulevard    | Miller Avenue               | 1 Driver Fatality                       | Will be part of AC Transit/OakDOT International Blvd Quick Built Project   | In Progress | 2                     |
| 7/1/2023      | 90th Avenue                | Plymouth Street             | 1 Motorcyclist Fatality                 | Install flex posts to close off median   | Installed   | 7                     |
| 7/3/2023      | 45th Avenue                | Bancroft Avenue             | 1 Passenger Fatality                    | Install additional red curbs and no parking signage, refresh all existing red curbs, and replace faded parking restriction signs   | Installed   | 5                     |
| 7/5/2023      | 85th Avenue                | San Leandro Street          | 1 Pedestrian Fatality                   | No engineering action identified   | n/a         | 7                     |
| 7/12/2023     | International Boulevard    | 29th Avenue                 | 1 Bicyclist Fatality                    | Will be part of AC Transit/OakDOT International Blvd Quick Built Project   | In Progress | 5                     |
| 8/6/2023      | Lakeshore Avenue           | Hanover Avenue              | 1 Bicyclist Fatality                    | Install newly developed sign for door zone near existing parking signs to remind drivers to look out for cyclists before opening door.   | Installed   | 2                     |
| 9/8/2023      | International Boulevard    | 9100 Block                  | 1 Pedestrian Fatality                   | No engineering action identified   | n/a         | 7                     |
| 9/16/2023     | 90th Avenue                | Plymouth Street             | 1 Motorcyclist Fatality                 | Install flex posts to close off median   | Installed   | 7                     |
| 9/24/2023     | 73rd Avenue                | Holly Street                | 1 Driver Fatality, 1 Passenger Fatality | No engineering action identified   | n/a         | 6                     |
| 9/26/2023     | International Boulevard    | 54th Avenue                 | 1 Pedestrian Fatality                   | Will be part of AC Transit/OakDOT International Blvd Quick Built Project   | In Progress | 5                     |
| 9/26/2023     | Seminary Avenue.           | 99 feet N of Outlook Avenue | 1 Pedestrian Fatality                   | Install high-visibility crosswalk striping and edge line delineator flex posts, add flex post for median area downhill and restore missing chevron and sign spacing, add reflective sign posts for chevron signs.                | Installed   | 6                     |
| 10/25/2023    | International Boulevard    | 200 ft E of 42nd Avenue     | 1 Pedestrian Fatality                   | Refresh red curbs and install new parking restriction signage  | Installed   | 5                     |
| 11/10/2023    | 98th Avenue                | 373 ft N of Empire Rd       | 1 Bicyclist Fatality                    | Design of improvements underway  | In Progress | 7                     |
| 11/14/2023    | International Boulevard    | 58th Avenue                 | 1 Pedestrian Fatality                   | Will be part of AC Transit/OakDOT International Blvd Quick Built Project   | In Progress | 6                     |
| 12/1/2023     | Martin Luther King Jr. Way | W Grand Avenue              | 1 Pedestrian Fatality                   | No engineering action identified   | n/a         | 3                     |

## 2023 Rapid Response Investigations and Status

| Incident Date | Location                |              | Fatal/Injury Category | Rapid Response Improvement   | Status      | City Council District |
|---------------|-------------------------|--------------|-----------------------|--|-------------|-----------------------|
|               | Major Street            | Cross Street |                       |  |             |                       |
| 12/28/2023    | International Boulevard | 7600 Block   | 1 Pedestrian Fatality | Will be part of AC Transit/OakDOT International Blvd Quick Built Project | In Progress | 6,7                   |